College Phone No.-9134595655
Principal Mobile - 8093392749

Website - www.plasseycollege.ac.in
Email Id - plasseycollege@gmail.com

PLASSEY COLLEGE

Estd.-2010

(affiliated to the University of Kalyani)

Mira Bazar, P.O.-Plassey, Kaliganj Block, Dist.-Nadia, Pin-741156, West Bengal, India.

Ref. No..... Date.....

NOTICE INVITING TENDER NO. 15 OF 2023-24 Dated 05.01.2024

E-Tenders are hereby invited by the undersigned for the following work from eligible agencies as per particulars given below:

1)	Name of work	:	Finishing work of Ground Floor of Educational Building (Annex Building- II) of Plassey College at Mira Bazar , Plassey, L.R. Plot No-296,302,303,345 under Mouza Uttar Hazrapota, J.L. No. 06 P.S.-Kaliganj in the district of Nadia
2)	Name of the Concerned Office	:	Plassey College, P.O.-Plassey, Dist – Nadia, Pin- 741156
3)	Estimated amount	:	Rs4320909.00 (inclusive of all taxes)
4)	Time of Completion of work	:	90 days from the date of acceptance of Work Order
5)	Contractors eligible to submit tenders	:	Bona-fide contractors & NGOs having GSTIN, PAN and I. Tax return certificate (A.Y. 20-21,21-22, 22-23)
6)	Place for submission of Tender document	:	Through www.wbtender.gov.in
7)	Date of Publication of NIT	:	06.01.2024, 11.00 a.m.
8)	Last date & time limit for submission of Tender	:	19.01.2024, 02:00 p.m.
9)	Date & time for opening of tender	:	Technical Bid- 21.01.2024, 2:00 p.m: Financial Bid- To be notified later
10)	Earnest money	:	Rs. 86418.00
11)	Validity of the Tender	:	The offer will remain valid for acceptance for 120 days from the date of receipt of tender

12) Conditional tender will be liable for rejection.

13) Cost over-run and consequent cost escalation for any material, labour, etc. will not be allowed.

14) No Ad-Interim Payment /mobilization advance/ secured advance will be allowed.

15) In case of inadvertent typographical mistake found in the specific price schedule of rates, the same will be treated to be so corrected as to confirm with the prevailing relevant schedule of rates and/ or technically sanctioned estimate.

16) Interested agencies are required to quote the rate in figure as well as in words mentioning percentage above/ below or AT PAR on the basis of relevant price schedule of probable items with approximate quantities.

17) Contractors shall have to comply with the provisions of (a) the contract Labour (Regulation Abolition) Act, 1970 (b) Apprentice Act 1961 and (c) Minimum Wages Act, 1948 or the modification there or any other laws relating thereto and the rules and order issued there under from time to time.

18) The payment will be made in 03 (three) installments. First & Second R.A. bills may be paid after completion of 50 and 80 percent of entire project and the third and final payment may be paid after the completion of entire project and to the satisfaction of the college construction committee. Contractors are requested to quote their rates accordingly. All the payment shall be made vide online transfer or account payee cheque.

Scanned with OKEN Scanner

19) The interested agencies will have to provide self-attested photocopies of PAN Card, latest Income Tax return, latest Professional Tax Clearance Certificate, GSTIN Certificate which will be valid up to the date of opening of the tender papers and other Credential Documents (within last 5(five) years from the last date of submission of tender documents) along with the Tender Paper.
20) Registered Labour Co-Operative Societies Ltd. will have to provide self-attested photocopies of current Audit Report, No Objection Certificate in support of their registration, Bye-laws, PAN Card, latest Income Tax Clearance Certificate, GSTIN Certificate, other Credential document (not less than 40% of the estimated amount in a single job and other documents for having experience of executing similar nature of work within last 5(five) years from the Last date of submission of tender papers).

21) Representation in Tender in connection with tender submitted by Co-Operative Societies:- The Chairman and the Secretary or three directors including either the Chairman or the Secretary shall execute and sign all deeds, documents, tender papers as per act of the Bye-Laws of the Co-Operative Societies, failing which the tender will be liable for rejection. The copy of last Audit Report (full) including copy of the minutes of last A.G.M has to be submitted along with application for verification of the authority.
22) In case of partnership firm, the interested agencies shall produce authentic document in respect of firm registration obtained from the Registrar of firms, West Bengal pursuant to the Indian Partnership Act – 1932 (Act IX of 1932) along with application (Deed made by Notary will be allowed).
23) No credential will be considered unless it is supported by payment certificate, work order and completion certificate mentioning the date of completion issued by the competent authority.
24) No person will be allowed to quote rate on the basis of Legal Power of Attorney conferred to him by the Firm/ Agency except in circumstances where necessary Govt. approval has been obtained.
25) The college authority shall be at liberty to take such legal action or actions as they deem fit and proper, in the event the agencies' submitted documents and credentials are found false and fake.
26) Incurred Income tax, GST and labour CESS shall be deposited by the agency itself under their respective registration numbers and its related certificate/challans (photocopy) shall be submitted to the undersigned as per Govt. norms.
27) The tender for the works shall remain open for acceptance for a period of 120 days from the date of N.I.T. If any agency withdraws his/her tender before the cited period or before the date of issue of work order/ letter of acceptance, whichever is earlier, or make any modification in the terms and condition of the tender which are not acceptable to the college authority, then the college authority shall, without prejudice to any other right or remedy, be at liberty to forfeit the entire earnest money . Further, the agency shall not be allowed to submit any tender in this Department for a minimum period of one year.
28) Earnest money is to be deposited online through ICICI Bank Payment Gateway. Please refer Memo No. 3975-F(Y), dated-28.07.2016 of the Finance Department, Govt of West Bengal.
29) No material will be supplied to the agency by the college.
30) Security Deposit (3%) and Earnest Money (2%) will be refunded after <u>one year</u> from the date of completion of the work. No earlier claim will be entertained.

Plassey College ESTD-2010 Mirabazar,P.O.-Plassey,Dt.-Nadia

05/1/24

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner

PROBABLE COST FOR ~~ESTIMATE~~ SCHEDULE WITH APPROXIMATE QUANTITIES FOR THE SCHEME,"Finishing work of Ground floor of Educational Building (Annex Building-II) of Plassey College At Mira Bazar, Plassey, L.R. Plot No- 296,302,303,345. under Mouza Uttar Hazrapota,J.L. No. 06 P.S - Kaliganj in the district of Nadia."

Civil

Sl.	Description of Work		Rate		Unit	Amount
1	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. Above lintel	9.04 m^3	Rs.447.00	Rupees Four Hundred FourtySeven Only	m^3	Rs.4,040.88
2	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. Step	23.14 m^2	Rs.327.00	Rupees Three Hundred TwentySeven Only	m^2	Rs.7,566.78
3	Cement concrete with graded stone ballast (40 mm size excluding shuttering) In ground floor (A) [Pakur Variety](a) 1:3:6 proportion Step	2.53 m^3	Rs. 4,938.00	Rupees Four Thousand Nine Hundred ThirtyEight Only	m^3	Rs.12,493.14
	(b) 1:4:8 proportion Col for Mumpty Room	4.63 m^3	Rs. 4,518.51	Rupees Four Thousand Five Hundred Eighteen Paise FiftyOne Only	m^3	Rs.20,920.70
4	Brick-work with 1st class bricks in cement morter (6:1) in (a) In foundation and plinth for out side Step	1.53 m^3	Rs.4,906.70	Rupees Four Thousand Nine Hundred Six Paise Seventy Only	m^3	Rs.7,507.25
	B. IN SUPERSTRUCTURE OF Ground FLOOR	23.88 m^3	Rs.5,128.70	Rupees Five Thousand One Hundred TwentyEight Paise Seventy Only	m^3	Rs.122,473.36
5	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor. Toilet	89.14 m^2	Rs.21.00	Rupees TwentyOne Only	m^2	Rs.1,871.94
6	Reinforcement for reinfroced concrete work in all sorts of structures including distribution bars,stirrups ,binders etc, initial straighening and removal of loose rust (if necessary), cutting to requisite length,hooking and binding to correct shape placing in proper position an binding with 16 guage black annealed wire in every intersection,complete as per drawing and direction. i) In Ground Floor	0.43 MT	Rs.54,400.74	Rupees FiftyFour Thousand Four Hundred Paise SeventyFour Only	MT	Rs.23,392.32
7	Ordinary cement concrete (Mix 1: 1.5 : 3 with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any as per relevant IS code. i) Ground Floor	5.54 m^3	Rs. 6,066.02	Rupees Six Thousand SixtySix Paise Two Only	m^3	Rs.33,605.75
8	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (c) Steel shuttering or 9 to 12 mm thick approved quality ply board shuttering in any concrete work	40.22 m^2	Rs.365.00	Rupees Three Hundred SixtyFive Only	m^2	Rs.14,680.30
9	Labour for Chipping of concrete surface before taking up Plastering work. Roof	1351.19 m^2	Rs.21.00	Rupees TwentyOne Only	m^2	Rs.28,374.99
10	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] Ground Floor. (i) With 1:6 cement mortar.(b) 20 mm thick plaster(Internal)	1365.16 m^2	Rs.165.00	Rupees One Hundred SixtyFive Only	m^2	Rs.225,251.40

05/1/24

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner

Civil

Sl.	Description of Work		Rate		Unit	Amount
	(ii) With 1:6 cement mortar.(b) 15 mm thick plaster(External)	668.24 m^2	Rs.144.00	Rupees One Hundred FourtyFour Only	m^2	Rs.96,226.56
	iii) With 1:4 cement mortar(c) 10 mm thick plaster(Internal)	727.24 m^2	Rs.128.00	Rupees One Hundred TwentyEight Only	m^2	Rs.93,086.72
11	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. GI to PI 0.00 m^2	136.55 m^2	Rs.34.00	Rupees ThirtyFour Only	m^2	Rs.4,642.70
12	Supplying, fitting & fixing best quality digital printed Ceramic tiles in coloured decorative on walls and floors to match with the existing work & 4 nos. key stones (10mm) fixed with adhesive 4.5 mm thick at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. With polymerised adhesive and epoxy grout pointing including spacer - 2mm (When tiles are laid over existing hard ready surface) all complete as per direction of Engineer-in-charge.	231.42	Rs.1,060.00	Rupees One Thousand Sixty Only		Rs.245,305.20
13	Supplying and laying true to line and level Double Charge Vitrified Tiles of approved brand conforming to IS 15622: 2006 (Group B I a) and tested as per IS 13630:2006 (relevant parts) [Non-modular sizes for tiles with Water Absorption (av.) ≤ 0.08 %] in floor, skirting etc. using polymerised adhesive of 6mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course and joints grouted with admixture of white epoxy grout materials of approved brand including spacer -2mm as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete as per direction of Engineerin-Charge.(Note: This work should not be executed without specific permission of Superintending Engineer) Ground Floor	274.31 m^2	Rs.1,566.00	Rupees One Thousand Five Hundred SixtySix Only	m^2	Rs.429,569.46
14	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour.(ii) 25 mm. thick Ground Floor Class Room	459.25 m^2	Rs.313.15	Rupees Three Hundred Thirteen Paise Fifteen Only	m^2	Rs.143,814.14
15	Supplying, fitting and fixing 18 mm. to 22 mm. thick kota stone slab in wall, dado in 15 mm thick [avg] cement mortar (1:3) including making suitable arrangement to hold the stone properly by brass / copper hooks including pointing in cement mortar (1:2) (1 cement : 2 marble dust) with admixture of pigments matching the stone shade, including grinding and polishing all complete as per direction of Engineer-in-charge including cost of materials, labour, scaffolding, staging, curing complete. [Using cement slurry for bedding @4.4 kg/Sq.m and for jointing @1.8 kg/Sq.m] Ground Floor	67.32 m^2	Rs.1,148.00	Rupees One Thousand One Hundred FourtyEight Only	m^2	Rs.77,283.36
16	Extra cost of labour for prefinished and premoulded Nosing to treads of steps, railing, window sill etc. of Kota Stone. Ground Floor	92.60 m	Rs.224.00	Rupees Two Hundred TwentyFour Only	m	Rs.20,742.40
17	Extra cost of labour for grinding Kota Stone Floor in treads and riser of Steps. Ground Floor	67.32 m^2	Rs.209.00	Rupees Two Hundred Nine Only	m^2	Rs.14,069.88
18	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame exluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be correted upto three decimals). (e) Sal : Malayasian	0.86 M^3	Rs.76,096.00	Rupees SeventySix Thousand NinetySix Only	M^3	Rs.65,442.56

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner

Civil

Sl.	Description of Work		Rate		Unit	Amount
19	Supplying solid flush type doors of deluxe decorative (both side) quality, conforming to I:S 2202 timber frame consisting of top and bottom rail and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 27.5mm wide battens places both ways in order to made the door of solid core and internal lipping with teak, mahogony or rose wood approved decorative veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing the shutters in position but excluding the cost of hinges and other fittings in ground floor (a) 35mm thick shutters (single leaf)	34.44 m^2	Rs.3,955.00	Rupees Three Thousand Nine Hundred FiftyFive Only	m^2	Rs.136,210.20
20	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to safisfy IS: 4020 door testing performance criteria.. (i) 66mm x 90mm	45.00 M	Rs.497.00	Rupees Four Hundred NinetySeven Only	M	Rs.22,365.00
21	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. (i) 32 mm thick	10.80 m^2	Rs.2,763.00	Rupees Two Thousand Seven Hundred SixtyThree Only	m^2	Rs.29,840.40
22	Collapsible gate with 40mm x 40mm x 6mm Tee as top and bottom guide rail, 20mm x 10mm x 2mm vertical channels 100mm apart in fully stretched position 20mm x 5mm M.S. flats as collapsible bracings properly rivetted and washered including 38mm steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc. in walls, floors etc. and making good damages complete. In ground floor.	23.73 m^2	Rs.3,402.00	Rupees Three Thousand Four Hundred Two Only	m^2	Rs.80,729.46
23	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or cencrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing (b) Two Coats.ii) Solvent based interior grade Acrylic Primer interior surface at G.F.	2092.40 m^2	Rs.4,850.00	Rupees Four Thousand Eight Hundred Fifty Only	%m^2	Rs.101,481.40
24	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothning of surface. Two Coats	2092.40 m^2	Rs.70.00	Rupees Seventy Only	m^2	Rs.146,468.00
25	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or cencrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC.(b) Two Coats	668.24 m^2	Rs.4,510.00	Rupees Four Thousand Five Hundred Ten Only	%m^2	Rs.30,137.62
26	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat).a) Normal Acrylic Emulsion	668.24 m^2	Rs.67.00	Rupees SixtySeven Only	m^2	Rs.44,772.08
27	Supplying 1.5mm thick M.S. sheet fitted and fixed on one or both faces of M.S./ W.I. gate etc. with point welding at not more than 150mm apart complete in all respect as per design including cost of all labour and materials. (a) On new wood work	4.62 m^2	Rs.977.00	Rupees Nine Hundred SeventySeven Only	m^2	Rs.4,513.74
28	Supplying fitting and fixing M.S. clamp for fixing door and window frame made of flat bent bar, end bifurcated, with necessary screws etc by cement concrete with stone chips (1:2:4) complete as per direction. (Cost of concrete will be paid seperately) i) 40 mm X 6 mm of 12.5 cm length A. In Ground Floor	200.0 Nos	Rs.22.00	Rupees TwentyTwo Only	each	Rs.4,400.00
29	Iron Butt hinges of approved quality fitted and fixed with steel screws with ISI marks.			Rupees		Rs.4,700.00

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner

Civil

Sl.	Description of Work		Rate		Unit	Amount
	a) 100 X 58 X 1.90 mm Door- D (Single leaf)	100.00 Nos	Rs.47.00	FourtySeven Only	each	Rs.4,700.00
30	Anodised aluminium Aldrop / Silding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/ 66) fitted and fixed complete.	25.00 Nos	Rs.231.00	Rupees Two Hundred ThirtyOne Only	each	Rs.5,775.00
31	Anodised aluminium barrel/ tower/ socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws: a)225 mm long X 10 mm dia bolt	50.00 Nos	Rs.84.00	Rupees EightyFour Only	each	Rs.4,200.00
32	Supplying fitting and fixing Hinged cleat in position excluding the cost of hinge and other fittings. a) 50mm iron butt hinge (local Sal)			Rupees FourtySeven Only		Rs.752.00
33	Wooden 125 mm long buffer block(local Sal) of approved size and quality.	16.00 Nos	Rs.54.29	Rupees FiftyFour Paise TwentyNine Only	each	Rs.868.57
34	Anodised aliminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: (a) With continuous plate base (hexagonal/round rod) 150mm grip x 10mm dia rod.	32.00 Nos	Rs.97.00	Rupees NinetySeven Only	each	Rs.3,104.00
35	Godrej Hydraulic door closer fitted and fixed complete. Medium Type	3.00 Nos	Rs.1,665.00	Rupees One Thousand Six Hundred SixtyFive Only	each	Rs.4,995.00
36	(a) Supplying 'Godrej' mortice lock chromium plated with latch and keys 4 levers, including fitting and fixing complete.	3.00 Nos	Rs.1,081.00	Rupees One Thousand EightyOne Only	each	Rs.3,243.00
37	Supplying, fitting and fixing Stainless Steel railing consist of 38mm dia and 900mm height vertical balustrade at every two alternative steps, 50mm dia top rail, 3 (three) nos 19mm dia horizontal Strainless steel pipe and base/cover plate with Strainless Steel GRADE 304 containing 7.5% nickle (Interior Grade) Brushed/Mat finish, complete as per direction of the Engineer-in-charge. Weight of Strainless Steel railing per metre 6.5 Kg (approx) A. In Ground Floor	12.00 m	Rs.7,677.00	Rupees Seven Thousand Six Hundred SeventySeven Only	m^2	Rs.92,124.00
38	Supplying fting and fixing windows and ventilators with or wotout integrated grills conforming to IS 1038-1975 and manufactured from rolled steel sections conforming to IS 7452-1974 with non-friction projecting type, box type hinges, glazing clips, lugs locking bracket, handle plate etc, including hoisting in position, straitning if required, fixing lugs in cement concrete (4:2:1) with stone chips 19 mm down cutting holes and mending good damages to match with existing surface complete in all respect excluding glazing. Openable steel windows as per IS sizes with side hunge shutters and horizotal glazing bars, with or outhout fixed type ventolators (the extra rate admissible for the openable portion only.)	58.32 m^2	Rs.2,199.00	Rupees Two Thousand One Hundred NinetyNine Only	m^2	Rs.128,245.68
	D. Two point nose steel handle including fitting and fixing. A. In Ground Floor	166.00 Nos	Rs.50.00	Rupees Fifty Only	Each	Rs.8,300.00
	E. Steel peg stay 300 mm long including fitting and fixing. A. In Ground Floor	166.00 Nos	Rs.35.00	Rupees ThirtyFive Only	Each	Rs.5,810.00
	M.S. integrated grill as per approved design integrated with steel window or ventilator, joints continuously welded with M.S. flats and bars. A. In Ground Floor 10 mm sq. guard bar @ 90 mm C/C	816.48 Kg	Rs.94.00	Rupees NinetyFour Only	Kg	Rs.76,749.12
39	Supplying, fitting and fixing in position fibre glass panes of approved quality with resin, nail, clip etc. as per IS:12866-1989. (In all floors for internal wall & upto 6 m height for external wall) d) 3.0 mm thick (5.10 Kg/Sq.m)	54.96 m^2	Rs.1,381.00	Rupees One Thousand Three Hundred EightyOne Only	m^2	Rs.75,899.76

15/1/24

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner

Civil

Sl.	Description of Work		Rate		Unit	Amount
40	Priming one coat on timber, plastered or on steel or other metalled surface with synthetic enamel or oil bound primer of approved quality including smoothening surface by sand papering etc.	34.56 m^2	Rs.38.00	Rupees ThirtyEight Only	m^2	Rs.1,313.28
	B) Steel or other metalled surface Surface	83.06 m^2	Rs.31.00	Rupees ThirtyOne Only	m^2	Rs.2,574.86
41	Two coats painting with best quality synthetic enamel paint of approved make and brand (With Super gloss Hi-gloss of approved quality any shade except white) including smoothening surface by sand papering etc.(iv) Two coats (with any shade except white) (a) On timber or plastered surface :	34.56 m^2	Rs.81.00	Rupees EightyOne Only	m^2	Rs.2,799.36
	B) Steel or other metalled surface Surface	83.06 m^2	Rs.79.00	Rupees SeventyNine Only	m^2	Rs.6,561.74
42	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materails (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete.A) UPVC Pipes:(iii) 160 mm. Dia.	60.00 m	Rs.485.00	Rupees Four Hundred EightyFive Only	m^2	Rs.29,100.00
	TOTAL					Rs.2,750,395.06

Add S & P Works upto @ 15.0%	on	Rs. 2,750,395.06	Rs.412,559.00
Add Electrictal Part -I			Rs.178,915.00
Add Electrictal Part -II			Rs.283,663.00
			Rs.3,625,532.06
Add G.S.T @ 18.0%	on	Rs. 3,625,532.06	Rs.652,596.00
		Total :	Rs.4,278,128.06
Add Cess @ 1.0%	on	Rs. 4,278,128.06	Rs.42,781.00
		Total	**Rs.4,320,909.06**

Payment may be made as per mode of measurement and specification of P.W.D. Schedule of works (All districts of West Bengal and Darjeeling Plain of Siliguri Sub-Division/ Nadia) (Volume -I (for building, material & labour)) of rates w.e.f. 01.11.2017 since with 15th corigendum.

05/1/24

Principal
Plassey College
Mirabazar, P.O.-Plassey,Dt-Nadia

Scanned with OKEN Scanner